

Price list of drum dryers STANDARD UNI
wood chips, sawdust, cereals, fodder

Drum dryer, type: STANDARD UNI	*SPB2 UNI*	*SPB5 UNI*	*SPB10 UNI*	*SPB20 UNI*	*SPB30 UNI*	*SPB30+UNI*
Capacity ≥50% humidity sawdust	≥250kg/h	≥500kg/h	≥1000kg/h	≥2000kg/h	≥2800kg/h	≥3500kg/h
SPB UNI dryer assembly	**68.500,-**	**99.500,-**	**113.500,-**	**144.500,-**	**174.500,-**	**260.500,-**
***3.** Automatic ash removal (EUR)*	2.600,-	2.600,-	3.500,-	3.500,-	4.100,-	4.100,-
***5.** Boiler cyclone separator (EUR)*	2.500,-	3.000,-	3.500,-	3.900,-	4.500,-	5.500,-
***6.** Electrostatic spark and dust precipitator (EUR)*	6.750,-	6.750,-	8.500,-	8.500,-	12.950,-	16.150,-
***R.** Control system and SW for full automatic operation (EUR)*	11.700,-	12.100,-	13.600,-	13.600,-	15.700,-	18.600,-
TOTAL SPB UNI dryer assembly (EUR)	**92.050,-**	**123.950,-**	**142.600,-**	**174.000,-**	**211750,-**	**304.850,-**
Optional accessories for SPB UNI dryers						
***7.** Silo - dried material silo 1x4m3 (EUR) -1pcs*	7.800,-	7.800,-	9.500,-	10.500,-	10.650,-	11.350,-
***7.1** Dried material hooper 1x 2m3 (EUR)*	7.800,-	8.400,-	9.000,-	9.600,-	11.800,-	13.400,-
***7.2** Auger feeding conveyor (EUR)*	11.600,-	11.600,-	11.600,-	13.300,-	13.300,-	14.200,-

The dryer set includes: 1.KDV UNI hot air boiler, **2.**Fuel storage tank volume 1.5 m3, **4**.Emergency chimney flap, **12.**Three-chamber drying cylinder, **13**.Frame supporting structure of the cylinder, **14.**Discharge screw conveyor with dispenser, **15**.Exhaust fan, **16**.Cyclone separator, **17**.Cyclone turnstile, **18**.Discharge screw conveyor, **19**.Connecting piping, **20**.Air and moisture exhaust, **21**.Exhaust of flue gases from the emergency flap, **22**. Exhaust of flue gases from the boiler. 10, 11







Prices are valid until 31.12.2026, price in EUR without VAT. The price does not include the transport of the equipment to the installation site, transport and accommodation of workers (2 technicians), assembly and commissioning. These prices will be calculated individually according to the installation site and will be charged separately.